




FOREST LAKE BOAT RAMP MIDTERM MEETING



Scope

- Boat Ramp Design w/ Cost Estimate(s)
 - Permit Guidance
 - Potential Grant Opportunities
 - Summarizing Report
-
- Questions/Concerns?

Alternative 1 – Status Quo

- Details
 - Leave situation as is
 - Not ideal, mainly for reference

Alternative 2 – Mobi-Mat

- Details
 - 20" stakes included
 - Available widths: 10', 13.8'
 - Available lengths: 16.5', 33', 50'
 - Rated for 40,000 lbs/in2
- Cost Breakdown
 - 10'x16.5': \$2,953
 - 10'x33': \$5,125
 - 13.8"x33': \$8,146
- <https://news3lv.com/news/local/adaptive-boat-ramp-launches-at-lake-mead>



Alternative 3 – FAUN C-40 Trackway

- Details
 - Available widths: 11', 13.75'
 - Length: customizable
 - Supports axle loads up to 28,655 lbs
- Cost Breakdown



		Length		
		20'	30'	50'
Width	11'	\$16,000	\$20,000	\$21,000
	13.75'	\$18,000	\$23,000	\$34,000

- https://vimeo.com/246431765?embedded=true&source=video_title&owner=20627751


FAUN C40 Accessories

Parbuckling Strap




Pushframe

Designed to roll out and recover up to 164ft (50m) of C40 or C90 Trackway® rapidly, by use of a compatible host machine with a quick hitch or suitable hitch.



Pushbar

With a strong tolerance to sea waters, the Pushbar can deploy up to 131ft (40m) of C40 Trackway® or 98ft (30m) of C90 Trackway® by use of vehicle with a towing capacity of 7,716lb (3,500kg).



Potential Locations for Temporary Mat

- #1 – Gradual yard where previous launch was
- #2 – Launch on East side of wet area
 - Dredging potential
- #3 – David & Andrea Meurer's existing private grass ramp
- Others?



Alternative 4 – Wetland Excavation / Mitigation

- Details
 - Dredge to deepen existing channel
 - Flexamat Surface
- Cost Breakdown
 - Dredging: \$17,000
 - Flexamat: \$22,000
 - Gravel base: \$800
 - Permitting:
 - application fee: \$800
 - mitigation cost: \$7,100
 - TOTAL: \$47,500



Alternative 5 - Boardwalk

- Details
 - Supports 10,000 pounds
 - Treated Wooden Posts would be used for posts w/ 10' wide alternative.
 - Most likely material would be concrete/wood composite
 - Through Permatrek
 - Would need gravel turnaround
- Cost Breakdown
 - Estimate would be \$85/SF w/Treated Timber Foundation
 - General estimate would be around \$200,000 for this magnitude



Potential Surveyor Analysis

- If permanent alternative is selected there would have to be a surveyor's analysis
- Assure work is being done on FLIA property
- Potential portion of site outside of wetland





Alternative Analysis



Any Questions?